



NOTES:

1. ALL MATERIALS EXCEPT CONCRETE AND BEDDING MATERIAL SHALL BE COMPACTED IN 6-INCH MAXIMUM LIFTS TO 95% DENSITY AS DETERMINED BY ASTM D1557.
2. KEEP TRENCH BOTTOM COMPACTED WITH UNIFORM GRADE. NO TEMPORARY SUPPORTS, I.E. BLOCKS, WILL BE ALLOWED TO SUPPORT PIPE. TRENCH BOTTOM SHALL BE TO GRADE PRIOR TO PIPE INSTALLATION.
3. TRENCH SHALL BE PLATED UNTIL PAVED.
4. PLATE TO BE SECURED BY METHOD APPROVED BY ENGINEER.
5. SPALLED OR DAMAGED CONCRETE SHALL BE RE-SAWN AND REPLACED TO LIMITS DIRECTED BY ENGINEER.

CEMENT CONCRETE PAVEMENT TRENCH RESTORATION

STANDARD PLAN:
ST - 030

DATE: **FEB. 2007**

CITY ENGINEER APPROVAL:

Longview: **C.B.**

Kelso: **S.Z.**